



Local Solar Inspection Checklist for the Naugatuck Valley Region

Applies to installations under 1MW.

This checklist is intended as a guideline. Please reference the NEC and IRC for updated code information.

- 1.** Ensure all PV disconnects and circuit breakers are in the open position before beginning work.
- 2.** PV module model number, quantity, and location are according to the approved plan.
- 3.** Array mounting system and structural connections are according to the approved plan.
- 4.** Roof penetrations flashed/sealed according to the approved plan.
- 5.** Array exposed cables are properly secured, supported, and routed to prevent physical damage.
- 6.** Conduit installation according to NEC 690.31(A) and the approved plan.
- 7.** Firefighter access according to IRC R324.7 and the approved plan.
- 8.** Roof-mounted PV mounting system and modules have sufficient fire classification [IRC R324.6.1].
- 9.** Grounding/bonding of rack and modules according to the manufacturer's instructions.
- 10.** Equipment installed, listed, and labeled according to the approved plan (e.g., PV modules, inverters, dc-to-dc converters, rapid shutdown equipment).
- 11.** For grid-connected systems, inverter is marked "interactive" or documentation is provided to show that inverter meets utility interconnection requirements.
- 12.** Conductors, cables, and conduit types, sizes, and markings according to the approved plan.
- 13.** Overcurrent devices are the type and size according to the approved plan.
- 14.** Disconnects according to the approved plan and properly located as required by the NEC.
- 15.** Inverter output circuit breaker is located at opposite end of bus from utility supply at load center and/or service panelboard. If panel is center-fed, inverter output circuit breaker can be at either end of busbar [NEC 705.12(B)] (not required if the sum of the inverter and utility supply circuit breakers is less than or equal to the panelboard bus rating).
- 16.** PV system markings, labels, and signs according to the approved plan.
- 17.** Connection of the PV system equipment grounding conductors according to the approved plan.
- 18.** Access and working space for operation and maintenance of PV equipment such as inverters, disconnecting means and panelboards (not required for PV modules) [NEC 110.26].
- 19.** The rapid shutdown system is installed and operational according to the approved plan [NEC 690.12].
- 20.** Assure all markings are permanently secured in place required by NEC.

Document last revised 3/4/22.